

SOP-40 — Compressor Operation & Lubrication

Plant: Shakti Petrochem Unit-2 | **Applies To:** Compressor | **Revision:** Rev 2 | **Last Reviewed:** 2025-01-30

Procedure Steps

1. Verify lube-oil level above minimum before start.
2. Monitor inter-stage temperature; investigate above 140 degC.